







# **Installation Manual**

**TerraGen Environmental Group** 

120 Parson Rd.

Alliston, Ontario, L9R 1E9

705-435-7373

Version: 18/05/2022



# **Table of Contents**

1.	General				
2.	Material Receiving				
3.	Tools Required				
4.	System Components				
5.	Annual Maintenance Activities 5				
6.	5. Installation of System 6				
6.1	6.1 Prep Work & Pre-assembly6				
6.1.	1	Tilt Assembly Installation	6		
6.1.	2	Cutting Rails	6		
6.2	Base	e Rail Installation	6		
6.2.	1	Base Rail Layout	6		
6.2.	2	Rubber Pad Installation	7		
6.2.	3	Base Rail Splicing	9		
6.3	Тор	Rail Installation	9		
6.3.	1	Cross Adapter Setup	9		
6.3.	2	Top Rail Layout	1		
6.3.	3	Top Rail Splicing	2		
6.3.	4	Top Rail Thermal Breaks	2		
6.4	Ballast Installation				
6.5	.5 Home Run Wiring				
6.6	6.6 Module Installation				
Appendix A: Ballast Requirements					
Appendix B: Bonding & Grounding					
Appendix C: Installation Efficiencies					
Appendix D: Wire Management Options					
Appendix E: MLPE Mounting					
Appendix F: UL 2703 Fire Classification					



#### General 1.

The TGR System is designed to be installed on a flat or low sloping roof for an array of any size, provided the guidelines within this manual and any other applicable codes and standards are followed. It is a rail-based design intended to secure 2-8 modules per rail, with continuity through splicing to create a grid-system. The system can be installed in landscape or portrait orientation for PV modules up to 45" X 90", provided the project specific design has been done accordingly and the module manufacturer guidelines are followed. To ensure proper installation and prevent a void of your warranty, the installation manual and the project specific documentation must be followed. In unique or custom cases where alternative components or design is required, the project specific documentation will supersede the installation manual where there is insufficient or conflicting information.

#### **Material Receiving** 2.

A detailed bill of lading will be sent with the shipment of racking. The receiver must confirm that all parts received are according to the detailed Bill of Lading and Packing Slip. Any damage must be noted on the bill of lading upon receipt. Any discrepancies must be reported within 2 business days. Otherwise, all claims will be invalid. If there are any damaged parts or rails, please provide a picture as well as documenting it on the Bill of Lading.



#### 3. **Tools Required**

5/16 socket (for Tek screw), 13mm deep socket (for 8mm nut)	
13mm Open-Ended / Combo Wrench	
5mm Metric Allen Key OR 5mm Allen Key Socket	or or
Socket wrench with matching drive for each of the above (i.e. 3/8 or 1/2" drive) OR Cordless drill and socket adapter for each of the above	or +
Chalk line and measuring tape	+
7 ft-lb and 12 ft-lb pre-set slip type torque wrenches OR an adjustable torque wrench	or
Miscellaneous	<ul><li>Onsite cutting ability</li><li>Cold galvanizing spray</li></ul>

- Use of impact tools when installing clamps and hardware will cause galling (seizing of SS hardware). TerraGen will not free issue components damaged from use of impact tools.
- All fasteners must be torque marked after applying the required torque.





#### 4. **System Components**



# **TGR System** 6, 11 & 13 not shown





The activities described below for the maintenance of the solar racking provided by TerraGen must be performed a minimum of every 12 months from the date of installation up until the system has been decommissioned. Records with images of the inspection must be recorded and kept.

- Perform a visual inspection of the system to check all components for any signs of defect. Any components showing signs of damage that compromise safety shall be replaced immediately.
  - o Check for any deformation, penetrating corrosion, or other noticeable defects in the components.
  - Inspect roofing condition around the contact points with the roof and that the system has not moved over time. Ensure appropriate roof protection is still secured appropriately in place.
  - o Ballast (when applicable) is secured as intended with no cracks or degradation.
  - Modules are seated correctly and secured.
- Check all hardware for specified torque or torque marks. Any loose components or fasteners shall be re-tightened in accordance with the installation instructions.




# 6. Installation of System

### 6.1 Prep Work & Pre-assembly

#### **6.1.1 Tilt Assembly Installation**

Assemble the tilt assemblies onto the base rails using the M8 - 50 mm bolt through the pre-drilled holes and securing with the M8 serrated nut. Start with installing one tilt assembly at the North and South of every base rail that has been laid out. Each bolt shall be torqued to 7 ft-lbs.



A is where tilt assemblies are placed. B is space between tilt assemblies. S + N = B in most cases. N and S represent the amount of base rail left over at the North end and South end, respectively.



Base Rail Side View

#### 6.1.2 Cutting Rails

Please refer to the Construction Package for the cuts required for the project, it is advantageous to set up a cutting station to prep all of these before installation.


#### **6.2** Base Rail Installation

#### 6.2.1 Base Rail Layout

Locate the starting point for the first base rail according to the Construction Package. The remainder of the base rails can be located in reference to the starting base rail with




proper center to center spacing from the Construction Package, by measuring or using a spacing jig. No additional measurements are absolutely required to align the front and back base rails, though a string or laser line can be helpful.



#### 6.2.2 Rubber Pad Installation

A rubber pad is used to protect the roof membrane. Place the rubber pad underneath the base rails before the placement of rails. Typical rubber pad supply is a recycled rubber under the base rails that is not attached to the system. TPV Rubber pad can be requested as a substitute, for which see below for installation instructions.








#### **TPV Rubber Pad Installation (Only applicable to TPV Rubber Substitution)**

TPV Rubber pad is to be slid onto the flanges of the base rails following the rubber coverage requirement from the Construction Package. To ensure the rubber slides on properly, the tilt assemblies must be installed first, and the rail should be flipped upside down for ease of sliding. Best practice is to use a sawhorse for the tilt assemblies & the rubber pads as the first step of the installation.



Roof warranty holder should be contacted to ensure compatibility with the roof membrane and ensure the roof warranty is maintained, if applicable.

Typical coverage is 30" pcs of the rubber pad spaced 30" apart. If any part of the base rail is contacting the roof in locations without the rubber pad, shift the rubber pad accordingly to protect contact points ensuring that a minimum of 3" has been left for drainage.

Ensure that all edges of the base rail are protected by the rubber pad.

Alternative rubber coverage can be accommodated at customer's request.





#### 6.2.3 Base Rail Splicing

To connect adjacent base rails four M8 - 50mm bolts are to be used to fasten the base rail splice over the 2 base rails.



#### **Roof Slope Changes**

If minor roof slopes cannot be accommodated with four bolts, the method shown below can be used. This method below adds eight #10-3/4" self tapping screws.






#### **Top Rail Installation** 6.3

#### 6.3.1 Cross Adapter Setup


Use cross adapters to secure the top rails to the tilt assemblies. Click the cross adapter onto the tilt assembly to attach a top rail. Unless otherwise specified on the



Construction package, 2 cross adapters per connection are only required on the edge of the base rails while all other connections in the field will require just 1 cross adapter. Refer to the diagram below to further describe the configuration pattern and the alternating sequence between inside and outside configurations in the field.




Use the pattern shown (below, right) to attach cross adapters on both sides of each rail for farthest east and farthest west columns. All other interior columns receive cross adapters on the insides of top rails, or outsides of top rails, in alternating sequence.



(C) Cross Adapters on outsides of top rails

Find this distance "d" in the Construction Package.





Pattern for Cross Adapters when there are more than 3 base rails



#### **6.3.2** Top Rail Layout


Top rails should be installed in the locations specified by the top rail layout plan. The layout plan can be found in the Construction Package. Please refer to it for top rail cut lengths and positions.





Top Rail Starting Layout Plan


The maximum overhang amount is also specified in the construction package and it is measured from the edge of the mounted panel to the base rail. A minimum of 2" of top rail is required past the end of the module on the starting side.






#### 6.3.3 Top Rail Splicing

When required, the top rails get spliced together with a bonding integrated splice bar. Ensure that the top rail is stopped by screw head and that the bonding clip is engaged with the aluminum from both rails. Where thermal breaks are required, a ¾" gap must be maintained between the ends of the top rails.



#### **6.3.4** Top Rail Thermal Breaks

In the case of extended rows, where a thermal break is required (refer to Construction Package), a module break is required divided by two end-clamps and a splice.




Due to undulations on the roof surface, the angle between the thermal break and the rails may be too large (>2 deg) to allow sliding of the rails on the splice. If this occurs, then the splices on either side of the rail which are not thermal breaks should be Tek screwed to lock them in place.



#### 6.4 **Ballast Installation**


Secure blocks with the provided ballast clamp in the appropriate locations according to the ballast plan on the Construction package. Please refer to the ballast block drawing for further information located in the Construction Package.




TGR Assembly with Ballast

#### **Ballast Tray Alternative**

If ballast trays are required utilize the configurations below corresponding to the ballast plan of the Construction package.







TGR Assembly with 4 Block Ballast Tray

#### 6.5 **Home Run Wiring**

After top rail installation is complete, this would be the best time to run all PV cable and home runs as this allows the installer to have free range of access to the racking for securing the PV cable.





#### 6.6 Module Installation


Install the modules by first clicking the end clamps onto the end of the top rails. Adjust the module to the proper position and tighten the end clamps to 7 ft-lbs. Next, click the mid clamps and bonding washer onto the top rail (refer to *Appendix B*).

Slide the mid-clamp in tight to the module making sure that the tab of the bonding washer is placed under the module frame. Once the next module is placed properly, the mid clamp can then be secured and torqued to 12 ft-lbs.

In the circumstance where the modules being installed have 50mm frames, care needs to be taken when installing mid clamps and end clamps as the bolt will be on its last few threads. Hand loosen the bolt prior to installing on rail.









WEEB CCR2 (Upon Request)

See construction package for details on clamp zones. TerraGen makes every attempt to ensure that the module clamping zones of the module manufacturer are met. However, ultimately it is the responsibility of the customer to verify that the module warranty will be maintained.



## **Appendix A: Ballast Requirements**

The TGR Ballasted System has been designed utilizing concrete blocks that range from 30-33 lbs. Provided components are designed to these dimensions, and any discrepancy with the block size will alter the function of these components. While these standard sizes are recommended for use with the TGR system, custom sizes can be accommodated upon review and approval by TerraGen. Refer to the project specific construction package for ballast weight, quantity, and placement.


#### Notes:

- 1. RANGE OF DIMENSIONS (D x H x W): 15 3/8" x 7 1/2" x 3 1/2" to 15 9/16" x 7 1/2" x 3 5/8"
- 2. **ALLOWABLE WEIGHT VARIANCE:** ± 0.32 kg (0.71 lbs)
- 3. Dimensions may slightly vary depending on location of blocks



#### **Mechanical Attachments**

An alternative method of uplift/lateral resistance is the use of roof attachments. TerraGen's system is compatible with various attachment options. One example of an attachment is shown below. Refer to the project specific construction package for details if attachments are required.






# **Appendix B: Bonding & Grounding**

The system has been evaluated/certified for Grounding/Bonding, and conforms to UL 2703. Refer to 'Module Listings' document for modules that have been certified to LTR AE-001-2012 and UL 2703.

#### **Connection 1: Module to Top Rail**

Mid-clamps with bonding washers bond rails to module frames with teeth piercing the anodized surface of the module.




#### **Connection 2: Top Rail to Top Rail**

In cases where two or more rails may need to be spliced together, top rails are spliced through a sliding splice which consists of a bonding clip that pierces the surface of the aluminum rails.



#### **Connection 3: Top Rail to Tilt Assembly**

Top rails are connected to tilt assemblies using cross adapters.



#### **Connection 4: Tilt Assembly to Base Rail**

Tilt assemblies connect onto the base rails using the M8 - 50 mm bolt through the pre-drilled holes and secured with the M8 serrated nut.



#### **Connection 5: Base Rail to Base Rail**

Four (4) M8 - 50mm bolts fasten through the pre-drilled holes of the base rail splice over 2 flush base rails and fasten with the M8 Serrated nut.



#### **Connection 6: Grounding Each Array**

Ilsco SGB-4 or other UL 467 listed Grounding Device (supplied by others) is used to ground the system. Provided the previously mentioned connections all apply; each individual array only needs to be grounded once (though 2 locations are suggested). Location for grounding device is often the back leg of the tilt assemblies or the excess end of a top rail.



# **Appendix C: Installation Efficiencies**

#### **Pre-Assembly of Tilt Assemblies on Base Rails**


If a holding rack is available, such as the one shown in the photo below, you may choose to use this method to speed up the assembly process.



Prior to hoisting the skid of tilt assemblies and the bundle of bottom rails to the roof of your building, take time to pre-assemble the tilt assemblies onto the bottom rail while still on the ground. Using sawhorses to hold the work piece at waist height, cut all necessary lengths. Refer to your Construction Package for lengths of base rails.

Telescopic Handler hoisting a holding rack with assembled base rails.

Once cut, place tilt assemblies onto the entire length, lining them up to the holes. Use the M8 bolt and serrated nut to fasten the tilt assembly in place. Torque to 7 ft-lbs. Place on holding rack. Ensure that the bundle is adequately secured to the holding rack for hoisting to the roof.





# **Appendix D: Wire Management Options**



**PHOTO #1:** East West rails can be used to secure PV wire. In this image, the installer has used PVC straps secure on the rail to support the PV wire.



**PHOTO #2**: Another option for securing the PV wire to the east west rails is the optional wire management clips that TerraGen offers.



**PHOTO #3:** PV wire management using the optional wire management clips on the solar panel.



PHOTO #4: TGR base rails, (the north south rails) can be used to secure wires requiring management from row to row. We permit installers to secure wire management components to our base rail. In this case the installer used PVC conduit.



**PHOTO #5:** Row to row DC wiring can be pulled through PVC conduit attached to the base rail and split loom wire protection.



**PHOTO #6:** TGR base rails can be used to support cable tray for wire support running from West to East.





# **Appendix E: MLPE Mounting**

T-Bolt assembly is available upon request from TerraGen to mount MLPE (microinverter or optimizer) into the channel of TerraGen rails. Ensure that guidelines from the MLPE installation manual are followed.







# **Appendix F: UL 2703 Fire Classification**

The system has been evaluated/certified for Fire Rating and has a UL 2703 Fire Class A rating for low slope roofs with Type I and Type II modules with the addition of the top rail on the Northern perimeter of each array. The system will perform as expected provided it is installed over a fire-resistant roof covering rated for the application.



#### **Fire Shield Installation**

